

Composite Valve and Pump Datasheet - Rev C

Synthetic supplier composite datasheet. Project aliases have been added in brackets.

1. Automated valve family

Property	Value
Type	2/2-way solenoid/pneumatic discrete valve
Command	24 VDC / Boolean open command
Fail action	Spring return CLOSED
Nominal opening time	0.7 s
Nominal closing time	0.5 s
Leakage at closed	<0.02% Kv
Permitted medium	Water / aqueous NaCl, 0-120 degC
Modelica abstraction	ValveDiscrete; no modulation

Project automated tags: V1, V3, V5, V6, V8, V9, V11, V12, V15, V18, V20, V22, V23, V24, V25. Valves not in this list are manual/local isolation, drain or cooling-water valves unless a later approved ICD assigns them to the controller.

2. Return pump family

Property	P1	P2
Service	Concentrate return	Condensate return
Nominal mass flow	0.30 kg/s	0.30 kg/s
Nominal differential pressure	1.8 bar	1.8 bar
Minimum source level permissive	LIS-701 >0.02 m	LIS-601 >0.02 m
Low discharge pressure alarm	PIS-901 <0.8 bar	PIS-1001 <0.8 bar
Dry-run policy	Inhibit start / trip	Inhibit start / trip

3. Installation note

Pump discharge headers are cross-connected to the charging-vessel return manifolds. Final routing is determined by the approved process-routing change record, not by pump physical location alone.